

MATERIAL IN PLACE

CR 550N; btw CR 900E & CR 1200E

Mainline Paving (3250 +- tons)	#9 surface (12.5 mm)	\$ _____/ton
Mainline Paving (6500 +- tons)	#5 base (25 mm)	\$ _____/ton
Approach Paving (300 +- tons)	#9 surface (12.5 mm) or #5 Base (25 mm)	\$ _____/ton
Compacted Aggregate (10,750 +- tons)	#53 base	\$ _____/ton
Geotextile, woven (37,000 +- SY)	Mirifi (500x or equiv)	\$ _____/sy
Transitional Milling (100 +- SY)	Variable Depth	\$ _____/sy
Tack Coat (7.7 +- tons)	AET Tack	\$ _____/sy
Calcium Chloride (26,000+-Gal)	38% Solution Spray on Aggr at .80 gal/SYD	\$ _____/gal
Compacted Aggr-shoulder stone (430+- tons)	#73 base	\$ _____/ton

CR 650E; btw US 50 & CR 800 N

Mainline Paving (7200+- tons)	#9 surface (12.5 mm)	\$ _____/ton
Mainline Paving (10800 +- tons)	#8 binder (19 mm)	\$ _____/ton
Approach Paving (430 +- tons)	#9 surface (12.5 mm) or #8 binder (19 mm)	\$ _____/ton
Mainline Milling (6600 +-)	2 inch (Millings delivered to Highway Dept.)	\$ _____/sy
Transitional Milling (390 +-SY)	Variable Depth	\$ _____/sy
Tack Coat (32 +- tons)	AET Tack	\$ _____/ton
Compacted Aggr-shoulder stone (980+-tons)	#73 base	\$ _____/ton

Notes:

1. Locations will be submitted for Community Crossings Grant Applications. The county reserves the right to reduce or eliminate projects based on funding availability.
2. INDOT Approved Mix Designs shall be used. Maximum RAP%: Surface – 0%, Intermediate/**Base – 15%**. No RAS shall be allowed.
3. INDOT Approved or Commercial Stone meeting INDOT requirement shall be acceptable.
4. Traffic control, signs, barricades, and flag persons shall be the responsibility of the bidder.
5. CR 550 N, CR 650 E projects shall be awarded separately.

Addendum No. 1 – Daviess County Annual Paving Bids 07/28/16

Addendum No. 2 - Daviess County Annual Paving Bids 08/04/16

Questions – Daviess County Materials in place bid

- Q. Can the contractor purchase stone off of the county's annual bid?
A. Yes. The contractor shall be responsible for coordinating with the county and chosen rock quarry. The county shall invoice the contractor based on current annual bid pricing. Current Annual Bid attached, prices will vary based on current fuel rates. The county rebid's stone in December 2016 for use in 2017.
- Q. Does the asphalt placed have to be caught up on both lanes at the end of each day?
A. Intermediate/Base – Yes Surface – No
- Q. Are barrels required on the edge of the roadway?
A. No
- Q. Can roads be closed to traffic during construction?
A. 650 E – No – Traffic shall be maintained during construction
550 N – Yes – Day closures will be allowed during construction. Roadway will need to be reopened at the end of each working day. Access shall be maintained to local traffic.
- Q. How will the calcium chloride be applied to the stone base on CR 550 N?
A. Calcium Chloride shall be applied in two applications of 0.40 Gal/SYD. The first application shall be applied after 4" of Compacted Aggregate Base is placed on the roadway and the second application shall be placed after the final 2" of compacted aggregate base is placed.
- Q. What is the Shoulder Stone Width?
A. 650 E - 1 foot.
550 N – 1 foot. County to pull existing earth shoulders to edge of pavement prior to placing stone shoulder. Contractor shall coordinate with county regarding timing.
- Q. Are there any paving exceptions?
A. 650 E – Paving Exception from paving joint south of CR 200 N to Bridge No 86. The length of this exception is approximately 3000 ft.
550 N – No exceptions. Project will start near the end of the existing pavement east of CR 900 E.
- Q. Which Approaches will be paved?
A. 650 E – Approaches in 2" Mill areas will not be paved. The following approaches will be paved: 100 N, 200 N, 280 N, 350 N, 400 N, 500 N, 550 N, 600 N, 750 N, and 800 N. The county shall grade existing gravel approaches prior to the contractor paving.
550 N – The following approaches will be paved: 975 E, 990 E, and 1100 E
Both Projects – Contractor shall gate out machine 1ft for existing driveways. Existing paved driveways may require wider area to provide smooth transition.
- Q. How will Geotextiles be placed and paid for on CR 550 N?
A. The geotextile will be placed to a width of 22'. The county will provide offset stakes. Payment will be made based on 2 - 12.5' wide rolls for the length of the roadway.